

Setting new standards in data centre management



All iPower products (passive and intelligent) are UK manufactured using UK components where ever possible and come with a 5 year warranty as standard. The objective is to offer the most accurate of power measurements within a PDU configuration that suits the customers requirements



The IT ACU versions offer the highest level of security encryption with SNMPv2 & 3 along with RADIUS, Telnet and Syslog. Information shown on the inbuilt touch screen TFT display along with remote screen option.



All units available in any socket quantity (subject to model), type or combination up to 125Amp single or 3 phase with a range of socket protection for use up to 60Deg (subject to model type) providing a reliable solution in any environment.



Along with the inbuilt WEB GUI offering real time information and alerts locally and remotely our free to download management package PDU Agent is available. This provides an entry level management system at no cost with no ongoing licence fees. In addition, MIB files for all the products are available for use with 3rd party DCiM applications.



Available in standard vertical or horizontal build formats or customised to meet clients specific requirements with regards to format, space limitation, colours or other factors. All variants use a calibrated resister (not CT coil) to provide the most accurate of monitored and calculated parameters. Can be constructed as in line units for use with legacy PDUs.



An array of environmental and security functions are available as standard depending on the product type. The IT ACU range is the most comprehensive supporting both temperature and humidity sensors, WEB cams, other closed contact applications such as water detection. In addition door sensors and electronic handles and key pads are supported. Remote displays are also available.



Following the latest quality EN62368 construction standards all units are assembled and tested by qualified personnel who have many year's experience in these products. In house test and compliance certification provided.



With the exception of the REM units, all of the iPower products can be mixed and matched and daisy chained with up to 32 devices per IP address. The PDU Agent software can support up to 50 different IP address.



While offering a 5 year warranty the IT range offers field replace management control boards and touch screen TFT display.



Our customer and technical service offers pre and post sale support to define a requirement and answer any technical questions going forward.

iPower Product Range

IP REM Single phase up to 32A overall monitored unit with any socket combination.

IP Lite Single phase up to 32A overall monitored with environmental capabilities

with any socket combination and can be daisy chained with up to 32 units.

IP ACU - IP1 Single or 3phase up to 125A overall monitored with environmental and security capabilities

with any socket combination and can be daisy chained with up to 32 units.

IP ACU - IP2 Single or 3phase up to 125A overall monitored and per socket monitored

with environmental and security capabilities up to 48 sockets and can be daisy chained with up to 32 units.

IP ACU - IP3 Single or 3phase up to 125A overall monitored and per socket monitored and switched

with environmental and security capabilities up to 48 sockets and can be daisy chained with up to 32 units.

IP ACU - IP4 Single or 3phase up to 125A overall monitored and per socket monitored and sequence switching with environmental and security capabilities up to 48 sockets and can be daisy chained with up to 32 units.

IP REM, IP Lite and ACU IP1 are available as in line units for use with legacy PDU's.

IP ATS 16/32A ATS switch with in line or socket options


IP DC A range of DC units designed as required with power monitoring (switching to follow)





















Setting new standards in data centre management

Product Features

UNIT CONSTRUCTION

Supplied with any type and quantity of sockets (IT2, 3 & 4 maximum 48 sockets)

Single phase/3phase up to 125A

Locking and none locking socket options. (Locking socket

- use standard power cords no special mating parts required)

Supplied with any length of mains lead and termination

Top, bottom, front or rear entry

Choice of mounting options or designed to meet specific fixing centre or dimensions

Range of power protection including individually fused socket, thermal trips, MCB, Hydromagnetic breakers

High operating temperatures

UK manufactured with 5 year warranty



POWER MONITORING & METERING

Accurate true power readings >1 by using calibrated resister

Overall readings of - RMS Volts, RMS Amps, Kilowats, Frequency PF (REM V/A/Kw/PF only)

Extended readings of - Peak volts, Peak current, kVA

Cumulative readings of - kWh, kJ/H, kg/CO2, BTU/h, consumption cost

Phase balancing measurements (breaker/3phase only)

Customer set threshold on key measured parameters (REM V/A/Kw/PF only)

SOCKET MONITORING

Per socket reading of - Amps, VA, Watts.

Customer set threshold on key measured parameters

Socket Switching

Individual socket switching (fail on)


Group setting for multiple socket on/off

Security setting to allow specific socket switching

Customer set threshold on key measured parameters

Individual socket switching (fail off) with sequence start functionality Group setting for multiple socket on/off with sequence start functionality





Up to 8 x Temperature sensors daisy chained – each with separate settings

Temperature & Humidity Sensor

Door Lock Port

Sensor Port

Key Pad Port

Remote Display Port - close contact port allowing 3 devices

USB port for WEB Cam or 2nd Network Connection

MANAGEMENT PROTOCOLS



10/100 Base T Ethernet port for network connectivity

Modbus port to allow up to 32 devices linked

RGB or TFT Display

Communications via: HTTP/HTTPS/HTML/CGI Telenet/SMTP/Syslog/Radius SNMPv2&3 IPv4&6

Full security access and alert setting

MID File available


Free PDU management software available (Up to 50 x IP address)






















Intelligent Monitoring Comparison

	IP1 Overall Monitoring	IP2 Overall + Individual Socket Monitoring	IP3 Overall + Individual Socket Monitoring + Switching	IP4 Overall + Individual Socket Monitoring + Switching	iPLite	iPowerREM						
KEY FLEXIBILITY												
Standard Build Spec	~	✓	~	✓	✓	✓						
Custom Build Capability (NO MOQ)	V	✓	✓	✓	✓	✓						
Custom Design Availability Full Manufacturer/Design Support within UK	Short Lead Time Yes	Short Lead Time Yes	Short Lead Time Yes	Short Lead Time Yes	Short Lead Time Yes	Short Lead Time Yes						
PDU INFO	162	162	162	162	162	162						
Rack Mount Vertical (OU)	✓	✓		✓	✓	✓						
Rack Mount Horizontal (1U+)	~	~	~	~	~	~						
Inline Unit	· · · · · ·	-	-	-	•							
Construction	Mild Steel	Mild Steel	Mild Steel	Mild Steel	Mild Steel	Mild Steel						
Finish	Powder Coated	Powder Coated	Powder Coated	Powder Coated	Powder Coated	Powder Coated						
Mains Lead Lead Length (Standard)	H07 3 Mtr	HO7 3 Mtr	H07 3 Mtr	H07 3 Mtr	H07 3 Mtr	HO7 3 Mtr						
Maximum Number of Sockets	∞	48	48	48	∞	∞						
Socket Types	C13, C19, Uk, Schuko, Plus Other											
ELECTRICAL CHARACTERISTICS												
Single/Three Phase Options	Both	Both	Both	Both	Single Phase Only	Single Phase Only						
Main Input Frequency	85 - 265 VAC 50 - 60 Hz	85 - 265 VAC 50 - 60 Hz	85 - 265 VAC 50 - 60 Hz	85 - 265 VAC 50 - 60 Hz	85 - 265 VAC 50 - 60 Hz	85 - 265 VAC 50 - 60 Hz						
Overall Meter Current Range	0 - 63 Amps	0 - 63 Amps	0 - 63 Amps	0 - 63 Amps	0 - 63 Amps	0 - 32 Amps						
Socket Current Range	- '	0 - 16 Amps	0 - 16 Amps	0 - 16 Amps	- '	- '						
Overall Meter Accuracy	+/- 1% Typical	+/- 1% Typical	+/- 1% Typical	+/- 1% Typical	+/- 1% Typical	+/- 1% Typical						
OVERALL MEASUREMENT												
RMS Volts	V	~	~	V	~	~						
RMS Amps	V	V	V	Y	V	Y						
Kilowatts Frequency	✓	✓	~	→	~	✓						
Power Factor	~	*	~	~	~	~						
Internal PDU Temperature	<u> </u>	~	~	~	~	~						
Peak Voltage	· ·	~	· ·	,	,	~						
Peak Current	V	V	V	✓	✓	V						
kVA	V	V	V	V	✓	V						
kWh (Cumulative)	✓	✓	✓	V	✓	✓						
Kg/CO2 (Cumulative)	-	-	-	✓	~	-						
BTU/h (Cumulative) KJ/h (Cumulative	*	V	Y	*	V	Y						
Cost (Cumulative)	~	~	~	~	~	✓						
OVERALL METER ACCURACY	•	•	•	▼	•	•						
Class II			~	✓	✓	~						
Billing Quality	~	~	~	~	~	~						
Sampling Rate 4000 times a second	· · · · · · ·	•	· · · · · ·	*	· · · · · ·	· · · · · ·						
INDIVIDUAL SOCKET MEASUREMENT												
Amps		~		✓								
Watts	-	· ·	·	<u> </u>	-	-						
VA	-	V	V	~	-	-						
kWh (Cumulative)	-	✓	✓	✓	-	-						
SOCKET CONTROL												
Individual Socket Switching	-	-	✓	✓	-	-						
Individual Socket Power Cycle	-	-	✓	✓	-	-						
Sequential Start Up (100 - 5000mS)	-	-	-	✓	-	-						
Programmable Startup Sequence (IP4 Only)	-	-	-	✓	-	-						
CONNECTIVITY												
Web GUI	✓	✓	✓	✓	✓	✓						
SNMP v1 and v2	Y	~	~	~	✓	✓						
SNMP v3 HTTP	✓	✓	~	~	- ~	- /						
HTTPs	~	~	~	~	-	-						
XML	Ÿ	· · ·	· ·	~	<u>-</u> ✓	<u> </u>						
Email Alerts	,	~	~	~	~	~						
IPv4	✓	✓	V	✓	✓	V						
IPv6	V	V	V	V	-	-						
TelNet	~	~	~	✓	✓	✓						
Syslog On Board Log Storage	V	✓	✓	√	-	-						
0 0	✓	✓	V	✓	-	-						
DAISY CHAINING												
RS485 Modbus - 1 Master up to 31 Slaves	~	✓	✓	✓	✓	-						
DISPLAY OPTIONS												
RGB Display Fitted within PDU	√ (1U)	√ (1U)	√ (1U)	√ (1U)	~	-						
Remote Display Option	V	✓	✓	✓	✓	-						
LED Display Graphical Display	- ✓ (1.5U+ / Vert)	- √ (1.5U+ / Vert)	- ✓ (1.5U+ / Vert)	- // (1 El I+ / \ / out)	-	✓						
arapriicat Disptay	▼ (1.5U+ / Vert)	▼ (I.5U+ / Vert)	▼ (1.5U+ / Vert)	√ (1.5U+ / Vert)	-	-						
	CAPABILITY ONLY,	SENSORS / ACCE	SSORIES AVAILAI	BLE SEPARATELY								
ENVIRONMENTAL SENSORS												
Temperature Sensor Port (Up to 8 Sensors)		✓	✓	✓	✓							
Humidity/Temperature Sensor	Ÿ	· ·	· ·	~	~	-						
Volt Free Contacts (3 Sets)	Ž	· ·	· ·	*	-	-						
CABINET SECURITY PORTS	•	•	•	•								
Door Contacts		✓	~	✓								
Electronic Door Handle	~	~	~	~	-	-						
Card Reader/Pin Pads	· · · · · · ·	· ·	· ·	*	-	-						
OTHER												
USB Port		✓	✓	✓	=	-						
	*	•	•									










Setting new standards in data centre management

IP1, 2, 3, 4 (ACU) – Port Identification



- Ethernet Port IEEE 802.3 with full 10/100Base-T network Compatability.
- Modbus Port High Speed MODBUS RS485 port for local daisy chaining of up to 32 PDUs.
- **Temperature Sensor Port** connect up to 8 Daisy Chained Temperature Sensors.
- Remote Display Port connect a secondary RGB Display for ease of viewing.
- **5 Local TFT 'Touch Screen' Display** Shows energy metrics, Some Environmental Metrics, Security Status and current IP Address, The display also relays alarm messages (if Required).
- **Humidity Sensor Port** Connect a Humidity / Temperature Sensor.
- Cabinet Door Lock Control Port Connect Electronic Handles, either purchase from us, or contact us to discuss integrating other handle manufacturers.
- Cabinet Door Card Reader Port Connect your Card Reader / Pin Pads, either purchase from us, or Contact us to discuss integrating your own Wiegand 26 Reader.
- Cabinet Door Contact Monitoring Port Connect door contacts to this port, either purchase from us, or contact us to discuss integrating your own door contacts.
- 10 Voltage Free Contacts 3 sets of Volt Free Contacts these are for the connection of any accessory contain a normally closed relay contact, e.g. Leak Detection, Smoke Detection, PIR.
- USB2.0 Port The USB port can be used to connect a small pin hole camera for security, or it can also be used for Automatic config upload, or as a small 5VDC PSU for connected accessories.
- Reset Button hidden beneath the label you will find a reset button, pressing this reboots the electronics (There is NO risk of power failure to connected equipment).
- **Default Button** hidden beneath the label you will find the default button, this enables a 'Factory Reset'. Please contact us for correct operation.


















Setting new standards in data centre management

IPLite – Port Identification



- Ethernet Port IEEE 802.3 with full 10/100Base-T network Compatibility.
- Modbus Port High Speed MODBUS RS485 port for local daisy chaining of up to 32 PDUs.
- Temperature Sensor Port connect up to 8 Daisy Chained Temperature Sensors
- Remote Display Port connect a secondary RGB Display for ease of viewing.
- Local RGB Display Backlit display shows energy metrics, Some Environmental Metrics, and current IP Address, the backlight can be configured to change colour in the event of an alarm condition.
- **Humidity Sensor Port** Connect a Humidity / Temperature Sensor.
- Reset Button hidden beneath the label you will find a reset button, pressing this reboots the electronics (There is NO risk of power failure to connected equipment).
- **Default Button** hidden beneath the label you will find the default button, this enables a 'Factory Reset' (Please contact us for correct opera on.

IPREM – Port Identification



- Ethernet Port (IEEE 802.3 with full 10/100Base-T network Compatibility.
- Local LED Display Four digit LED Display showing Volts, Amps, kWs, Power Factor, Frequency, and IP Address.
- Function 'PUSH' Button this button allows you to scroll though the Metrics that can be displayed Locally.
- Reset Button pressing this reboots the electronics (There is NO risk of power failure to connected equipment).
- Boot Button hidden beneath the label you will find the boot button, this enables the REM Meter to enter 'Bootloader mode' for the update of firmware. Please contact us for correct operation.



UK CE RO

















Setting new standards in data centre management

Mains Lead and Terminations

Each option of the IPower range of units can be manufactured with mains cable either top or bottom entry and to a length as required. The mains lead can be supplied in HO7, PVC, LSOH/LSZH, SWA or any other chosen specification and core number and size would meet the current characteristics of

the specific units. The mains lead termination for these leads can be into any connector type required (subject to physical fit). The mains lead can also be colour coded if required. We can also provide units with direct connections using a range of sockets (C14/C20/Neutric etc).

Sockets

Each option of the IPower range of units can be manufactured with any quantity* and combination or type of sockets. These include:



IEC C13 Type F



Individually Fused /



Locking



IEC C19 Type J



Individually Fused



Locking



BS1363 UK



Schuko



Neutric



NEMA





3Phase







UK Plug








NEMA

*On IP2, IP3 or IP4 build the maximum number of sockets is 48. Other socket types are available.























Setting new standards in data centre management

Accessories

Temperature and temperature and humidity sensor - Daisy chain 8 x Temperature sensor ports each with separate settings.

Units come with 3mtr lead as standard but other lengths available.

High/Low temperatures can be set and alerts reported or logged using PDU Agent.











Leak Tape available in 5mtr incremental lengths or as spot sensors as required. Any alert will be raised.

Door or panel sensor as required with alerts sent when contact is broken. If running PDU Agent times would be logged.

Handles with inbuilt or remote key pads connected into the IPower Units. No additional power requirements as release voltage taken from the PDU itself. An array of security access levels and up to 32 separate card users. Alerts can be set and full logging if running PDU Agent.

Shown is the Southco version but any Wegan based handle can be incorporated.

Any WEB based camera can be used either stand alone or used in conjunction with the door sensors.

Daisy Chain Kit

The IPLite units have IO ports to directly daisy chain up to 32 units on 1 x IP Address.

For the IT version there is a daisy chain kit available. The IT versions will also support 32 devices on any configuration over a single IP address.

Can mix and match any IPower products on the PDU Agent platform.

The Close contact port can take up to 3 close contact types of sensors against which alerts can be raised.

























Setting new standards in data centre management

PDU Build Check List

Please follow the simple check list to obtain the information required to provide an accurate quotation. If any doubt complete as best as possible or call.

CONSTRUCTION	Horizontal		Vertical	In-Line					
	Any colour requirements								
CURRENT	10amp	16amp	32amp	63amp	125amp	DC			
PHASING	1Ph	3Ph							
MAIN LEAD	Bottom Entry		Top Entry	У					
	Lead length in meters								
FUNCTIONALITY	Passive	No functionalityLocal Monitoring							
	Active	Overall Unit M Per Socket M Per Socket Sv Per Socket - S							
SOCKET OPTIONS		Socket types and Qty Qty Qty Qty Qty Qty dntity d		e mixed					
ESTIMATED NUMBER OF U	JNITS								
ANY SPECIAL INSTRUCTION	ONS								



Manufactured







